



**ELK CREEK FISH PASSAGE AND
SEDIMENT REDUCTION PROJECT
2025-1**

**ADDENDUM #3
ISSUED: April 21, 2025**

**THE FOLLOWING ADDITIONS, DELETIONS, AND/OR CHANGES SHALL BE
MADE AND INCORPORATED IN THE BID DOCUMENT.**

1. A new Bid Item, Bid Item 23. Road Repair, is added to the bid schedule.

23	Road Repair	3,000	SF	\$	\$
-----------	--------------------	--------------	-----------	-----------	-----------

Measurement for the Road Repair shall be based on the bid price per square foot of roadway requiring repair. Payments shall include full compensation for furnishing all materials, labor, equipment, incidentals, permits, and performance of all Work, including but not limited to Furnishing and installation of road repairs in accordance with the Construction Specifications Section 9 and Subsection 9.3 for patching and repairs. A complete and updated Bid Schedule is attached.

Bid Schedule

This Bid Schedule must be completed in ink and included with the sealed Bid Proposal. Pricing must be provided for each Bid Item as indicated. Items marked "(SW)" are Specialty Work that must be performed by a qualified Subcontractor. The lump sum or unit cost for each item must be inclusive of all costs, whether direct or indirect, including profit and overhead. The sum of all amounts entered in the "Extended Total Amount" column must be identical to the Base Bid price entered in Section 1 of the Bid Proposal form.

AL = Allowance CF = Cubic Feet CY = Cubic Yard EA = Each LB = Pounds
 LF = Linear Foot LS = Lump Sum SF = Square Feet TON = Ton (2000 lbs)

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
1	Mobilization/Demobilization	1	LS	\$	\$
2	Clearing and Grubbing	2	LS	\$	\$
3	Water Management	2	LS	\$	\$
4	Temporary access route	1	LS	\$	\$
5	Crossing 2 Upgrade w/ 30' X 16' prefabricated bridge	1	LS	\$	\$
6	Crossing 2 - Excavation	100	CY	\$	\$
7	Crossing 2 - Rock slope protection (RSP) (placed)	35	CY	\$	\$
8	Crossing 2 - Streambed material and bankline rock (placed)	25	CY	\$	\$
9	Crossing 2 - Compacted backfill and finished grade	55	CY	\$	\$
10	Crossing 2 - Road base and paving	1200	SF	\$	\$
11	Crossing 3 Upgrade w/ 9' X 80' aluminized CMP culvert (placed)	1	LS	\$	\$
12	Crossing 3 - Excavation	1700	CY	\$	\$
13	Crossing 3 -RSP (placed)	170	CY	\$	\$
14	Crossing 3 - Engineered streambed material (ESM) (placed)	100	CY	\$	\$
15	Crossing 3 - Compacted backfill and finished grade	500	CY	\$	\$
16	Crossing 3 - Road base & paving	2500	SF	\$	\$
17	Crossing 3 - Step rock (placed)	60	CY	\$	\$
18	Crossing 3 - Gravel augmentation	1	LS	\$	\$
19	Culvert disposal	2	LS	\$	\$
20	Planting and Maintenance	2	LS	\$	\$
21	Erosion control and mulch	2	LS	\$	\$
22	Seeding	2	LS	\$	\$
23	Road Repair	3000	SF	\$	\$
24				\$	\$

BID ITEM NO.	ITEM DESCRIPTION	EST. QTY.	UNIT	UNIT COST	EXTENDED TOTAL AMOUNT
25				\$	\$
26				\$	\$
27				\$	\$
28				\$	\$
29				\$	\$
30				\$	\$
31				\$	\$
32				\$	\$
33				\$	\$
34				\$	\$
35				\$	\$
36				\$	\$
37				\$	\$
38				\$	\$
39				\$	\$
40				\$	\$

* Final Pay Quantity

TOTAL BASE BID: Items 1 through _____ inclusive: \$ _____

Note: The amount entered as the "Total Base Bid" should be identical to the Base Bid amount entered in Section 1 of the Bid Proposal form.

BIDDER NAME: _____

END OF BID SCHEDULE